

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-21508-00-01
Spot: NESW Sec/Twnshp/Rge: 30-32S-15W
2278 feet from S Section Line, 2995 feet from E Section Line
Lease Name: BRASS Well #: 4
County: BARBER Total Vertical Depth: 4795 feet

Operator License No.: 0
Op Name: LANDOWNER
Address:

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4670		WITH 2 SX CMT
SURF	8.625	416		
COND	16	53		
PROD	4.5	4793	2300	

Well Type: EOR UIC Docket No: E22141.1 Date/Time to Plug: 04/15/2009 11:45 AM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: MARK MOGENSTERN Company: CLARKE CORPORATION Phone: (620) 886-5664

Proposed Plugging Method: CIBP @ 4675' WITH 2 SX CMT. PLUG AT 760' WITH 15 SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/15/2009 12:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4670' & PUT 2 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN 4 1/2" CASING & RUN 2 3/8" TBG TO PLUG THROUGH. 1ST PLUG AT 760' WITH 15 SX GEL & 50 SX CMT W/50# HULLS. 2ND PLUG AT 440' WITH 50 SX CMT & 50# HULLS. 3RD PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4725	4735		

INVOICED
DATE: 5-7-09
INV. NO. 2009061521

RECEIVED
APR 22 2009
KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED

APR 16 2009

KCC DODGE CITY

Signed

Stephen J. Pfeifer
(TECHNICIAN)

Form CP-23