

6 070152

API NUMBER 15-195-21, 489-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE-SE-SW, SEC. 36, T. 11 S, R. 25 (W)

230 feet from N section line

2310 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9087

Lease Name ULHUT Well # 1

Operator: R+C DRILLING INC

County TREGO

Name & Address P.O. BOX 296

Well Total Depth 4135 134.39 feet

HAYS, KANSAS.

Conductor Pipe: Size 8 5/8 feet 250

67601

Surface Casing: Size _____ feet

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor R+C DRILLING INC. License Number 1617

Address P.O. BOX 296 HAYS, KANSAS, 67601

Company to plug at: Hour: 3:00 ^{AM} Day: 17th Month: MAY Year: 19 84

Plugging proposal received from RICK FINNISY

(company name) R.C. DRILLING INC (phone) 913-625-4248

were: 8 5/8" - 250 FT SP. CUC #1/165 SK QUICK SET. - BY ALLIED CEMENTING.

ORDER 195 SK 50/150 Pozmix GEL - CA-CL - 1 SK CELLO FLAME AND 8 5/8" PLUG

SPOT WITH DRILL STEM - TURN HOLE OVER - HEAVY MUD BETWEEN ALL PLUG.

NO CIRCULATION PROBLEMS, ELV. 2496 - ANH. 2087', MARMINGTON

NO AIRBUCKLE

Plugging Proposal Received by [Signature] (TECHNICIAN) BOIC

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 4:30 ^{AM} Day: 17th Month: MAY Year: 19 84

ACTUAL PLUGGING REPORT ORDERED 195 SK 50/150 Pozmix GEL - CA-CL - 1 SK CELLO FLAME + 8 5/8" PLUG

SPOTTED WITH DRILL STEM - TURN HOLE OVER, HEAVY MUD BETWEEN ALL PLUG

1st Plug @ 2100 FT #1/25 SK CNT, 2nd Plug @ 1190 FT #1/100 SK CNT AND

1 SK CELLO FLAME MIXED IN. - 3rd Plug @ 270 FT #1/50 SK CNT.

4th Plug SOLID BRIDGE HULL'S - PLUG @ 40 FT #1/10 SK CNT, 10 SK RAT HOLE (OIR)

CEMENTED BY ALLIED CNT.

Remarks: _____ (If additional description necessary, use BACK of this form.)

INVOICED

DATE 5-22-84

WV. NO. 1623

RECEIVED
STATE CORPORATION COMMISSION
MAY 21 1984
5-21-1984
CONSERVATION DIVISION
Wichita, Kansas

Signed [Signature] (TECHNICIAN) BOIC