

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-195-21171-00-02
Spot: SESWNW Sec/Twnshp/Rge: 11-13S-21W
3147 feet from S Section Line, 4404 feet from E Section Line
Lease Name: HAMBURG Well #: 5
County: TREGO Total Vertical Depth: 4164 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 N MARKET STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	260	0	w/165 sxs cmt
PROD	5.5	3966	0	w/200 sxs cmt

Well Type: EOR UIC Docket No: E25700.1 Date/Time to Plug: 04/28/2009 9:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: GEORGE STOPPLEWORTH Company: DARRAH, JOHN JAY, JR. Phone: (620) 786-4046

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 500# hulls - 11 sxs gel.
DV at 1532' w/350 sxs. PBTD 3570'.
135.33

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/28/2009 2:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Alliance Well Service RIH with tubing to 3030'.
Copeland Cementing rigged to tubing - pumped 11 sxs gel - followed with 50 sxs 60/40 pozmix - 4% gel with 200# hulls mixed in.
Pulled tubing to 2050'. Copeland Cementing rigged to tubing - pumped 205 sxs cement with 300# hulls to circulate cement to surface.
Pulled tubing. Topped off 5 1/2" casing with 10 sxs cement.
Rigged to 8 5/8" casing - pumped 10 sxs cement.
Max. P.S.I. 350#. S.I.P. 350#.

Perfs:

Top	Bot	Thru	Comments
3498	3504		

RECEIVED
APR 30 2009
KCC WICHITA


INVOICED
DATE: 5-11-09

Remarks: COPELAND ACID & CEMENTING COMPANY-TICKET #35446.

INV. NO. 2009061526

Plugged through: TBG

District: 04

Signed 
(TECHNICIAN)

CM

PRT

APR 29 2009

7

JOHN JAY DARRAH, JR.
 405 CENTURY PLAZA
 WICHITA, KS 67202
 CONTR MALLARD DRLG. CO., INC. #5 HAMBURG 11-13-21W
 SE SW NW 00
 CTY TREGO
 GEOL _____ FIELD HOMBURG EXT (1/8 N)
 ELV 2157 KB SPD 4/7/83 CARD ISSUED 7/28/83 IP P 20 BOPD
 API 15-195-21,171 MARM 3784-3805

2970 FSL
 4290 FFL

+	+	+
+	+	+
+	+	+

LOG	Tops	Depth/Datum
ANH	1514+	643
B/ANH	1563+	594
TOP	3191-1034	
HEEB	3420-1263	
TOR	3438-1281	
LANS	3455-1298	
BKC	3702-1545	
MARM	3774-1617	
REW-ARB	3876-1719	
ARB	3922-1765	
GR WSH	4121-1964	
RTD	4126-1969	

8 5/8 " 251/165SX; 5 1/2 " 3966/200SX; DV TOOL AT 1532/350SX
 DST (1) 3476-3540 (LANS) / 15-20-15-20, REC 710' MSW, SIP 739-728#, FP 120-262 / 305-360#
 DST (2) 3608-3810 (LANS) / 40-40-40-40, REC 400' OCW, 645' OGW, 435' MSW, SIP 1040-1029#, FP 218-911#
 MICT - CO, PF (MARM) 3784-3805 W/1 SPF, AC 1000G, SWB LD, GSO, PF (LANS) 3644-3649 W/1 SPF, AC 500G, SWB LD, NON-COMMERCIAL, T&R, POP, PLUG OFF LANS PF'S - PROD FROM MARM ZN, P 20 BOPD, 6/27/83

COPYRIGHT 1983
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

NOTE: 6/16/83 - ORIGINALLY FIRST REPORTED IN NE NW NW