

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-159-03657-00-00  
Spot: NENESE Sec/Twnshp/Rge: 32-20S-7W  
2307 feet from S Section Line, 423 feet from E Section Line  
Lease Name: BARKER Well #: 3  
County: RICE Total Vertical Depth: 4000 feet

Operator License No.: 5610  
Op Name: BRUCE OIL COMPANY, L.L.C.  
Address: 1704 LIMESTONE RD  
MCPHERSON, KS 67460

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	225		
T1	2.875	3625	3490	TUBING PARTED
PROD	5.5	3743	1500	

Well Type: SWD UIC Docket No: D05550.0 Date/Time to Plug: 04/10/2009 10:15 AM  
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.  
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE, INC. Phone: (620) 628-4723

Proposed Plugging Method: SEE BELOW

130.00

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL  
Date/Time Plugging Completed: 04/21/2009 9:30 AM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

TUBING PARTED @ 3490'. POSSIBLE CASING COLLAPSED @ 3300' WHERE MILLED TO. RUN TUBING TO 3236' AND PUMP 75 SX'S CEMENT. RE-TAGGED ON 4-13-2009 @ 3176'. CUT CASING @ 1500' AND PULL OUT OF HOLE. RUN TUBING TO 1100' ON 4-20-2009 AND PUMP 35 SX'S CEMENT, PULL TUBING TO 600' AND PUMP 35 SX'S CEMENT-LET SET FOR AWHILE AND RE-TAGGED @ 470'. PULL TUBING TO 279' AND CIRCULATE CEMENT TO SURFACE. USED 275 SX'S CEMENT TOTAL. RE-CHECKED ON 4-21-2009 AND FOUND CEMENT STILL PRESENT AT TOP OF CASING, IN CELLAR.

Perfs:

Top	Bot	Thru	Comments
3743	4000	OH	

INVOICED  
DATE 5-11-09  
INV. NO. 2009061523

RECEIVED  
APR 30 2009  
KCC WICHITA

Remarks: COMMON CEMENT AND CALCIUM CHLORIDE. ALLIED CEMENT TICKET #36291.

Plugged through: TBG

District: 02

Signed

Virgil Clottier  
(TECHNICIAN)

JK

PKT