

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-119-10032-00-01
Spot: SENWSWSW Sec/Twnshp/Rge: 36-32S-30W
700 feet from S Section Line, 4781 feet from E Section Line
Lease Name: COLLINGWOOD Well #: 4 SWD
County: MEADE Total Vertical Depth: 3110 feet

Operator License No.: 7943
Op Name: WEST PLAINS ENTERPRISES, INC
Address: PO BOX 279
PLAINS, KS 67869

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1627		WITH 850 SX CMT
PROD	5.5	2866	0	WITH 200 SX CMT

Well Type: SWD UIC Docket No: D28329.0 Date/Time to Plug: 04/20/2009 12:30 PM
Plug Co. License No.: 34069 Plug Co. Name: BASIC ENERGY SERVICES, LP
Proposal Rcvd. from: ALLAN WALKER Company: WEST PLAINS ENTERPRISES Phone: (620) 563-6112

Proposed Plugging Method: TIE ON TO 5 1/2" CASING AND FILL WITH CEMENT. TIE ON TO 8 5/8" SURFACE CASING AND FILL WITH CEMENT.

101-08

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 04/21/2009 11:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

4/20/09: PUMP 200# HULLS & 325 SX CMT. DID NOT PRESSURE UP. CASING ON A VACUUM. SHUT DOWN TO LET CMT SET. 4/21/09: RAN WIRELINE. TOC @ 700'. PERFORATED AT 700'. PUMPED 200 SX CMT. CMT TO SURFACE. CMT TO SURFACE IN 5 1/2" CASING & TO SURFACE IN 8 5/8" ANNULUS.

Perfs:

Top	Bot	Thru	Comments
2866	3063	OH	

KANSAS CORPORATION COMMISSION

APR 29 2009

RECEIVED

INVOICED

DATE 5-11-09

INV. NO. 2009061537

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: CSG

District: 01

RECEIVED

APR 23 2009

KCC DODGE CITY

Signed

Jerry W. Stapleton
PART II

(TECHNICIAN)

Form CP-2/3

[Handwritten signature]