

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-053-20972-00-00  
Spot: SEWNWE Sec/Twnshp/Rge: 33-16S-10W  
4230 feet from S Section Line, 1406 feet from E Section Line  
Lease Name: SCHROEDER Well #: 6  
County: ELLSWORTH Total Vertical Depth: 3400 feet

Operator License No.: 9067  
Op Name: DAMAR RESOURCES, INC.  
Address: 234 W 11TH STE A PO BOX 70  
HAYS, KS 67601

| String | Size  | Depth (ft) | Pulled (ft) | Comment |
|--------|-------|------------|-------------|---------|
| SURF   | 8.625 | 411        |             |         |
| PROD   | 5.5   | 3400       |             |         |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/23/2009 1:00 PM

Plug Co. License No.: 32128 Plug Co. Name: ROME CORPORATION DBA WESTERN WELL SERVICE

Proposal Rcvd. from: EVAN WAVERLY Company: DAMAR RESOURCES INC Phone: \_\_\_\_\_

Proposed Plugging Method: SEE BELOW  
110.50

Plugging Proposal Received By: B. J. HOPE

Witness Type: PARTIAL

Date/Time Plugging Completed: 04/23/2009 3:00 PM

KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Perfs:

SET CIBP @ 2940' & CAP WITH 4 SX'S CEMENT. PERFORATE @ 1350', 1000' & 460'. RUN TUBING TO 1364' & PUMP 35 SX'S CEMENT WITH 100 LBS, COTTON HULLS, PULL TUBING TO 992' & PUMP 35 SX'S CEMENT WITH 100 LBS COTTON HULLS, PULL TUBING TO 465' & CIRCULATE CEMENT TO SURFACE. USED 145 SX'S CEMENT. CONNECTED ON TO BACKSIDE OF CASING & PUMPED 25 SX'S CEMENT-HELD PRESSURE @ 300 LBS. PLUGGED PER COMPLIANCE - DENIED T.A.

RECEIVED  
APR 30 2009  
KCC WICHITA  
INVOICED  
DATE: ~~04~~ 5-11-09  
INV NO. 2009061525

Remarks: 60-40 POZ, 4% GEL. QUALITY CEMENT TICKET #3088. L.K. WIRELINE TICKET #13386.

Plugged through: TBG

District: 02

Signed Virgil Clothier  
(TECHNICIAN)

124

PBT