

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-189-22681-00-00
Spot: NENWNE Sec/Twnshp/Rge: 33-33S-37W
330 feet from N Section Line, 1650 feet from E Section Line
Lease Name: WILLOUGHBY Well #: 33 #1
County: STEVENS Total Vertical Depth: 6675 feet

Operator License No.: 5278
Op Name: EOG RESOURCES, INC.
Address: 3817 NW EXPRESSWAY STE 500
OKLAHOMA CITY, OK 73112

String Size Depth (ft) Pulled (ft) Comments
SURF 8.625 1613 WITH 480 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/12/2009 5:00 AM

Plug Co. License No.: 34000 Plug Co. Name: KENAI MID-CONTINENT, INC.

Proposal Rcvd. from: _____ Company: _____ Phone: _____

Proposed Plugging Method: 1ST PLUG AT 1650' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

216.94

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 04/12/2009 7:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

1ST PLUG AT 1662' WITH 100 SX CMT. 2ND PLUG AT 658' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 20 SX CMT. 4TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 5TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

KANSAS CORPORATION COMMISSION
APR 29 2009
RECEIVED

INVOICED
DATE 5-11-09
INV. NO. 200

Remarks: USED 60/40 POZMIX 4% GEL BY HALLIBURTON.

Plugged through: DP


District: 01

RECEIVED

APR 14 2009

KCC DODGE CITY

Signed



(TECHNICIAN)

