

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-199-20073-00-00  
Spot: SWSWSW Sec/Twnshp/Rge: 33-15S-42W  
330 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: SMITH BS Well #: 2  
County: WALLACE Total Vertical Depth: 5250 feet

Operator License No.: 3273  
Op Name: LOEB, HERMAN L.  
Address: PO BOX 524  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1709	0	w/785 sxs cmt
PROD	5.5	5248	0	w/240 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/24/2009 11:00 AM  
Plug Co. License No.: 32997 Plug Co. Name: EASTERN COLORADO WELL SERVICE, LLC  
Proposal Rcvd. from: ED LOEB Company: LOEB, HERMAN L. Phone: (618) 943-2227

Proposed Plugging Method: Ordered 700 sxs 60/40 pozmix - 4% gel - 1000# hulls - 19 sxs gel.  
Plug through tubing.

170.63

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/24/2009 4:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 1709' w/785 sxs cement.  
5 1/2" production casing wet at 5248' w/240 sxs cement.  
CIBP set at 5050'. Production casing has holes.  
Production casing perforated at 2760' and 1680'.  
Ran tubing to 4990' - pumped 19 sxs gel followed with 50 sxs cement with 150# hulls.  
Pulled tubing to 2760' - pumped 200 sxs cement with 500# hulls.  
Pulled tubing to 1680' - pumped 350 sxs cement with 350# hulls.  
Cement circulated to surface from 5 1/2" production casing and 8 5/8" surface casing.  
Pulled tubing to surface.  
Connected to 8 5/8" surface casing - pumped 25 sxs cement.  
Cement circulated from 5 1/2" production casing.  
Plug complete.

Perfs:

Top	Bot	Thru	Comments
5124	5137		

INVOICED  
DATE: 5-11-09  
INV NO. 2009061530

RECEIVED  
APR 30 2009  
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #43,905.

Plugged through: TBG

District: 04

Signed Darrel Dipman  
(TECHNICIAN)

CM

Form CP-2/3

APR 27 2009

*Handwritten signature/initials*

REPLACEMENT CARD

PETROLEUM, INC.  
300 W. DOUGLAS, #800

#2 SMITH 'BS'

33-15-42W  
SW SW SW


WICHITA, KS. 67202

CONTR CHEYENNE DRILLING

CTY WALLACE

GEOLOGICAL BOB POSEY

FIELD STOCKHOLM SW EXT  
(1/8 N)



ELV 3873 KB SPD 11/11/85 CARD ISSUED 3/20/86 IP P 344 BOPD, NW  
3864 GL DRLG COMP 11/23/85 MRW 5124-5137  
API 15-199-20,073

SMP	Top	Depth/Datum
HEEB	.....	4118- 245
TOR	.....	4138- 265
LANS	.....	4216- 343
MRW SH	.....	5017-1144
MRW SD	.....	5108-1235
STE GEN	.....	5166-1293
PBTD	.....	5158-1285
RTD	.....	5250-1377

8 5/8 " 1709 / 765 SX, 5 1/2 " 5248 / 240 SX  
NO CORES  
DST (1) 4990-5160 (MRW) / 30-60-60-120, REC 562' SLI GCM,  
SIP 561-508#, FP 267-321 / 321-348#, HP 2275-2249#  
MICT - CO, PF (MRW) 5124-5137, W / 2 SPF, GSO, SET 2 7/8 "  
TBG AT 5156.25, POP, P 344 90PD (GR 44.5%), 1/2/86

INFO RELEASED: 4/30/87 - WAS OIL WELL - TIGHT HOLE

COPYRIGHT 1987  
INDEPENDENT OIL & GAS SERVICE, INC.  
WICHITA, KANSAS