

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-199-20085-00-00
Spot: SWSWNW Sec/Twnshp/Rge: 33-15S-42W
2970 feet from S Section Line, 4950 feet from E Section Line
Lease Name: SMITH BR Well #: 1
County: WALLACE Total Vertical Depth: 5252 feet

Operator License No.: 3273
Op Name: LOEB, HERMAN L.
Address: PO BOX 524
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1761	0	w/500 sxs cmt
PROD	5.5	5251	0	w/250 sxs cmt <u>170.69</u>

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/23/2009 1:00 PM
Plug Co. License No.: 32997 Plug Co. Name: EASTERN COLORADO WELL SERVICE, LLC
Proposal Rcvd. from: ED LOEB Company: LOEB, HERMAN L. Phone: (618) 943-2227

Proposed Plugging Method: Ordered 700 sxs 60/40 pozmix - 4% gel - 1000# hulls - 19 sxs gel.
Plug through tubing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/24/2009 11:15 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 1761' w/500 sxs cement.
5 1/2" production casing set at 5251' w/250 sxs cement.
CIBP at 5050'. Production casing has holes.
Production casing perforated at 2750' - 1730' - 200'.
Ran tubing to 5020' - pumped 19 sxs gel followed with 50 sxs cement and 150# hulls.
Pulled tubing to 2750' - pumped 200 sxs cement with 500# hulls.
Pulled tubing to 1750' - pumped 400 sxs cement with 250# hulls.
Cement circulated to surface from 5 1/2" production casing and 8 5/8" surface casing.
Pulled tubing to surface.
04/24/2009 - Topped 5 1/2" production casing with 25 sxs cement.
Connected to 8 5/8" surface casing - pumped 25 sxs cement.
S.I.P. 300#.

Perfs:

Top	Bot	Thru	Comments
5128	5132		
5107	5121		

RECEIVED INVOICED
DATE 5-11-09
APR 30 2009 INV. NO. 2009061530
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY-TICKET #43,904.

Plugged through: TBG

District: 04

Signed Darrel Dipman
(TECHNICIAN) CM

Form CP-2/3

APR 27 2009

PHS

PETROLEUM, INC.
300 W. DOUGLAS

REPLACEMENT CARD

33-15-42W
SW SW NW

WICHITA, KS. 67202


#1 SMITH 'BR'

CONTR CHEYENNE DRILLING

CTY WALLACE

GEOLOGICAL TOM ROBERTSON

FIELD STOCKHOLM SW EXT
(1/8 NE)



ELV 3864 KB SPD 5/12/86

CARD ISSUED 7/31/86

IP P 205 BOPD, NW

3855 GL DRLG COMP 5/18/86

MRW 5107-5132 OA

API 15-199-20,085

LOG	Tops	Depth/Datum
CO GR		3231 + 633
HEEB		4100- 236
TOR		4136- 272
LANS		4209- 345
BKC		4614- 750
CHER		4718- 854
ATOKA		4861- 997
MRW		5007-1143
STOCKHOLM SD		5104-1240
STOCKHOLM LM		5134-1270
STE GEN		5152-1288
PBD		5208-1344
RTD		5250-1386
LTD		5252-1388

8 5/8 " 1761 / 500 SX, 5 1/2 " 5251 / 250 SX
NO CORES

DST (1) 4994-5140 (MRW) / MISRUN
MICT - CO, PF (MRW) 5107-5121 & 5128-5132, GSO, T&R, POP,
P 205 BOPD, NW, 7/7/86

CORRECTION & INFO RELEASED: 8/21/86 - CORRECTED DST (1) -
WAS 4993-5142 & IP, ADDED TOPS

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS