

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-24977-00-00
Spot: NWSESE Sec/Twnshp/Rge: 28-12S-17W
990 feet from S Section Line, 990 feet from E Section Line
Lease Name: SCHMEIDLER WEST Well #: 4
County: ELLIS Total Vertical Depth: 3730 feet

Operator License No.: 5252
Op Name: NIXON, R P OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3600		
SURF	8.625	207	0	140 SX
PROD	5.5	3729	0	100 SX

121.23

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/21/2009 1:30 PM
Plug Co. License No.: 5252 Plug Co. Name: NIXON, R P OPERATIONS, INC
Proposal Rcvd. from: DUANE ACHTERBERG Company: NIXON, R P OPERATIONS, INC Phone: (785) 656-0038

Proposed Plugging Method: Ordered out 300 sxs 60/40 pozmix - 4% gel - 12 sxs gel spacer - 500# hulls.
Port collar at 1338' w/350 sxs cwc. CIBP at 3600'.

Plugging Proposal Received By: PAT STAAB WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/21/2009 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

Allied pumped 50 sxs 60/40 pozmix - 4% gel with 200# hulls - followed with 12 sxs gel spacer and 240 sxs cement with 300# hulls.
Max. P.S.I. 500#. S.I.P. 0#.
Shut in 30 minutes. Topped off 5 1/2" casing with 10 sxs. Casing full.
Backside full of cement.

Perfs:

Top	Bot	Thru	Comments
3574	3577		
3474	3477		
3422	3425		

INVOICED
DATE 5-11-09
INV. NO. 2009061535

RECEIVED
APR 27 2009
KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Richard Williams
(TECHNICIAN)

CM

Form CP-2/3

APR 23 2009

Pat

replacement card

Property of Ks Corp Comm

R P NIXON OPERATIONS
HAYS KS 67601

28-12S-17W
NW SE SE

4 SCHMEIDLER WEST

site: 3-1/4 N OF CATHERINE KS

city: ELLIS

API 15-051-24977

cont: SHIELDS DRILLING # 1

field: SCHMEIDLER

op: DAN A NIXON

tr date 08/12/97

well date 08/29/97

orig comp 10/07/97

card issued 01/12/98

last revised 06/15/98

ELV: 2126 KB, 2121 GL LOG	
tops.....	depth/ datum
* ANH.....	1332 + 794
* B/ANH.....	1370 + 756
TOP.....	3088 - 962
HEEB.....	3347 - 1221
TOR.....	3368 - 1242
LANS.....	3393 - 1267
BKC.....	3627 - 1501
ARB DOL.....	3676 - 1550
PBTD.....	3685 - 1559
LTD.....	3730 - 1604
RTD.....	3730 - 1604

IP status:

OIL, P 18 BOPD & WTR, LKC 3422-3576 OA, 11/01/97
 INFO RELEASED: 6/15/98 - WAS OIL WELL - TEMP
 COMP
 CSG: 8-5/8" 207 / 140 SX (ALT 2), 5-1/2" 3729 / 100 SX,
 PORT COLLAR AT 1338
 SHOWS: 3291-3304 (TOP LM, SCAT DEAD OIL STN,
 WET), 3372-3374 (TOR LM, SLI VUG PORO, TR RR SPTY
 STN, NSFO OR ODOR, 5% PORO), 3405-3407 (LANS LM,
 TITE, OCC PR INTRFOSSIL PORO, RR LT SPTY STN,
 NSFO OR ODOR, 14% PORO), 3422-3425 (LANS LM, FR
 VUG PORO, SATR STN, SSFO, FNT ODOR, 12% PORO),

COPYRIGHT 1998
 INDEPENDENT OIL & GAS SERVICE, INC.
 WICHITA, KANSAS

(over)

R P NIXON OPERATIONS
HAYS KS 67601

28-12S-17W
NW SE SE

4 SCHMEIDLER WEST

3441-3445 (LANS LM, TR SLI VUG PORO, TR SPTY STN, SSFO), 3463-3465 (LANS LM, TR SLI
 VUG PORO, TR SLI SPTY STN, NSFO OR ODOR, 12% PORO), 3476-3478 (LANS LM, PR TO OCC
 FR VUG PORO, SPTY STN, SSFO, ODOR, 9.5% PORO), 3558-3560 (LANS LM, TITE, FRAC'D IN
 PT, RR LT SPTY STN, TR DK SPTY STN, NSFO OR ODOR, 5% PORO), 3576-3578 (LANS LM, PR
 VUG
 PORO, SPTY STN, TR SATR STN, SFO, ODOR, 11% PORO), 3622-3624 (LANS LM, TITE TR PR
 INTRFOSSIL PORO, TR SPTY STN, NSFO OR ODOR, 4% PORO), 3676-3690 (ARB DOL, GD VUG
 PORO, OCC OOLTC PORO, SATR STN, GSFO, STR ODOR, 16%-17% PORO), 3690-3699 (ARB DOL,
 GD VUG PORO, OCC SPTY STN, SFO, ODOR, STNG DECR W/DEPTH),
 3699-3730 (ARB DOL, GD VUG PORO, SLI SO, OCC BARREN, WET)
 NO CORES OR DSTS
 TRGT ZN: LKC, ARB (OIL), PTD 3670 (ARB), MICT - CO, PF (ARB) 3676-3679, 3692-3695, AC EA
 ZN W/500 GAL (15% INS), REC ALL WTR, SET CIBP AT 3685, PF (LKC) 1/3423, 1/3475, 1/3575,
 AC 1500 GAL (20% NON-E), SO, RE-PF (LKC) 3422-3425, 3474-3476, 3574-3576, SET 2-3/8" TBG AT
 3675, NO PKR, POP, P 20 BO/24 HRS, IPP 18 BOPD & WTR, DOFP 11/1/97