

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-01643-00-01
Spot: NESESW Sec/Twnshp/Rge: 24-15S-12W
990 feet from S Section Line, 2310 feet from W Section Line
Lease Name: WOYDZIAK Well #: 1
County: RUSSELL Total Vertical Depth: 3332 feet

Operator License No.: 5252
Op Name: NIXON, R P OPERATIONS, INC
Address: 207 W 12TH
HAYS, KS 67601

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3255		
SURF	8.625	260	0	150 SX
PROD	5.5	3324	0	125 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/22/2009 9:30 AM
Plug Co. License No.: 5252 Plug Co. Name: NIXON, R P OPERATIONS, INC
Proposal Rcvd. from: DUANE ACHTERBERG Company: NIXON, R P OPERATIONS, INC Phone: (785) 656-0038

Proposed Plugging Method: Ordered 265 sxs 60/40 pozmix - 4% gel - 15 sxs gel - 500# hulls.
Perfs: 1300' - 760' - 460' 200'.

108-29

Plugging Proposal Received By: BRUCE RODIE WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/22/2009 12:15 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Tubing at 3207' - pumped 15 sxs gel and 50 sxs cement with 200# hulls.
Pulled tubing to 1300' - pumped 175 sxs cement with 300# hulls.
Cement circulated - closed backside and circulated cement out the braden head.
Pulled tubing out - filled casing with 23 sxs cement.

Perfs:

Top	Bot	Thru	Comments
3298	3302		
3193	3196		
3081	3084		
3031	3034		
3007	3009		
2926	2930		

KANSAS CORPORATION COMMISSION

APR 29 2009

RECEIVED

INVOICED

DATE 5-11-09

INV. NO. 2009061535

Remarks: QUALITY OILWELL CEMENTING COMPANY-TICKET #3074.

Plugged through: TBG

District: 04

Signed

Ray A Dinkel

(TECHNICIAN)

CM

Form CP-2/3

APR 23 2009

PKS

