

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
March 2009
This Form must be Typed
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 4419
Name: Bear Petroleum, Inc.
Address 1: P.O. Box 438
Address 2: _____
City: Haysville State: KS Zip: 67060 + _____
Contact Person: Dick Schremmer
Phone: (316) 524-1225

API No. 15 - 195-20266 -0001
If pre 1967, supply original completion date: _____
Spot Description: _____
NW- NENE Sec. 12 Twp. 13 S. R. 22 East West
4,950 Feet from North / South Line of Section
990 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: Trego
Lease Name: Herl Well #: 1

Check One: Oil Well Gas Well OG D&A Cathodic Water Supply Well Other: _____
 SWD Permit #: _____ ENHR Permit #: _____ Gas Storage Permit #: _____
Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks
Surface Casing Size: 8 5/8" Set at: 224 Cemented with: 160 Sacks
Production Casing Size: 5 1/2" Set at: 3896 Cemented with: 175 Sacks

List (ALL) Perforations and Bridge Plug Sets:

3623-28', 3645-48', 3661-63', Model D Packer @ 3715', 3726-30', 3745-50', 3761-71', 3785-91', 3807-14'

Elevation: 2266 (G.L. / K.B.) T.D.: 4051 PBTD: 3715 Anhydrite Depth: 1678

Condition of Well: Good Poor Junk in Hole Casing Leak at: Model D Packer @ 3715' (Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):

According to the rules and regulations of the KCC.

Is Well Log attached to this application? Yes No Is ACO-1 filed? Yes No

If ACO-1 not filed, explain why:

RECEIVED
APR 22 2009
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

Company Representative authorized to supervise plugging operations: Dick Schremmer - Bear Petroleum, Inc.

Address: P.O. Box 438 City: Haysville State: KS Zip: 67060 + _____

Phone: (316) 524-1225

Plugging Contractor License #: 3009 Name: Gressel Oil Field Service, Inc.

Address 1: P.O. Box 438 Address 2: _____

City: Haysville State: KS Zip: 67060 + _____

Phone: (316) 524-1225

Proposed Date of Plugging (if known): unknown

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 4-21-09 Authorized Operator / Agent: _____ (Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

Dick Schremmer
PKT

DAILY DRILLING REPORT

OPER. MACK OIL CO. NO. 1 FARM Herl
 CONT. Rains & Williamson Oil LOC. NW NW NE - Sec. 12-13S-22W
 ELEV. 2266' KB DF 2261' GL CO. Trego
 EST T.D. 4100' COMM. 5-13-74 COMP. 5-22-74 IP OIL

SAMPLE TOPS BY: Jay Dirks		LOG TOPS BY: Dresser	
Driller's Pick			
Anhydrite	1678 (+ 588)		
B/Anhydrite	1715 (+ 551)		
Heebner	3554 (-1288)	Heebner	3551 (-1285)
Lansing	3588 (-1322)	Lansing	3586 (-1320)
B/Kansas City	3828 (-1562)	B/Kansas City	3824 (-1558)
Pawnee	3927 (-1661)	Pawnee	3921 (-1655)
Conglomerate	4006 (-1740)	Conglomerate	4006 (-1740)
Arbuckle	4030 (-1764)	Arbuckle	4034 (-1763)
RTD	4050	LTD	4051

c.c. to: B-P Inv.; G. Eason; M. Marra; Norville Oil; E. Roberts; Mack Oil

5-14-74 Spudded @ 12:15 p.m. 5-13-74 Cut 234' 12 $\frac{1}{4}$ " hole. Ran 7 joints of 8 5/8" new 24# casing (216') set @ 224' w/160 sx. common cement, 2% gel, 3% CC. Plugged down @ 5:45 p.m. Drilling @ 675'

5-15-74 Drilling @ 2230'

5-16-74 Drilling @ 2720'

5-17-74 Drilling @ 3215'

5-20-74 DST #1 3616'-68' 30"-30"-30"-30" GTS - 1 hr. 35", Rec. 120' GCOM & 1580' Gassy Oil; FP's 94-590# BHP's 1136-1136#

DST #2 3711'-60' 30"-30"-30"-30" Weak blow for 10"-died; Rec. 15' M. FP's 0-23# BHP's 165-47# Temp. 115°

Drilling @ 3800'

5-21-74 Drilling @ 4030'

5-22-74 Preparing to run casing

5-23-74 Ran 123 joints of 5 $\frac{1}{2}$ " casing; set @ 3896' w/150 sx. common, 18% salt, 3/4 of 1% CFR2. Plugged down 10:30 p.m. 5-22-74. Final report.

RECEIVED
 APR 22 2009
 KCC WICHITA



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

BEAR PETROLEUM, INC.
PO BOX 438
HAYSVILLE, KS 67060-0438

April 27, 2009

Re: HERL #1
API 15-195-20266-00-01
12-13S-22W, 4950 FSL 990 FEL
TREGO COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

This notice is void after October 24, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.

Sincerely,

Steve Bond
Production Department Supervisor

District: #4
2301 E. 13th
Hays, KS 67601
(785) 625-0550