

**KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING APPLICATION**  
*Please TYPE Form and File ONE Copy*

Form CP-1  
March 2009  
**This Form must be Typed  
Form must be Signed  
All blanks must be Filled**

OPERATOR: License #: 33209  
Name: Penn Virginia Oil & Gas Corporation  
Address 1: Seven Sheridan Square, Suite 200  
Address 2: \_\_\_\_\_  
City: Kingsport State: TN Zip: 37660 + \_\_\_\_\_  
Contact Person: Jim Burns  
Phone: ( 423 ) 723-0230

API No. 15 - 017-20840-00-00  
If pre 1967, supply original completion date: \_\_\_\_\_  
Spot Description: \_\_\_\_\_  
NW<sup>4</sup> SW<sup>4</sup> - \_\_\_\_\_ Sec. 23 Twp. 21 S. R. 6  East  West  
1,980 Feet from  North /  South Line of Section  
660 Feet from  East /  West Line of Section  
Footages Calculated from Nearest Outside Section Corner:  
 NE  NW  SE  SW  
County: Chase  
Lease Name: Odle 23-12 Well #: 1

Check One:  Oil Well  Gas Well  OG  D&A  Cathodic  Water Supply Well  Other: CM  
 SWD Permit #: \_\_\_\_\_  ENHR Permit #: \_\_\_\_\_  Gas Storage Permit #: \_\_\_\_\_  
Conductor Casing Size: \_\_\_\_\_ Set at: \_\_\_\_\_ Cemented with: \_\_\_\_\_ Sacks  
Surface Casing Size: 8 5/8 Set at: 210 Cemented with: 150 Sacks  
Production Casing Size: 5 1/2 Set at: 3391 Cemented with: 180 Sacks

List (ALL) Perforations and Bridge Plug Sets:  
3298-3303; 3272-3275; 3265-3269; 3255-3259; 3212-3216; 3218-3222

Elevation: 1384 ( G.L. /  K.B.) T.D.: 3410 P.B.T.D.: 3390 Anhydrite Depth: \_\_\_\_\_  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Junk in Hole  Casing Leak at: \_\_\_\_\_  
(Interval)

Proposed Method of Plugging (attach a separate page if additional space is needed):  
POOH with pump and rods. Set tubing @3212'. Pump 50' of cement. Pull out and lay down tubing. Perf well @210'. Circulate cement from 210' to surface. Cut off and cap well.

Is Well Log attached to this application?  Yes  No Is ACO-1 filed?  Yes  No  
If ACO-1 not filed, explain why: \_\_\_\_\_

**RECEIVED  
APR 22 2009  
KCC WICHITA**

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission  
Company Representative authorized to supervise plugging operations: Jim Burns Penn Virginia Oil & Gas Corporation  
Address: Seven Sheridan Square, Suite 200 City: Kingsport State: TN Zip: 37660 + \_\_\_\_\_  
Phone: ( 423 ) 723-0230  
Plugging Contractor License #: 32701 Name: C & G Drilling, Inc.  
Address 1: 701 E River Address 2: \_\_\_\_\_  
City: Eureka State: KS Zip: 67045 + \_\_\_\_\_  
Phone: ( 620 ) 583-5318  
Proposed Date of Plugging (if known): \_\_\_\_\_

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent  
Date: 4/20/2009 Authorized Operator / Agent: JAMES R. BURNS James Burns  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*KCC*  
*Diary 2*  
*Pkt*



CORPORATION COMMISSION

Kathleen Sebelius, Governor Thomas E. Wright, Chairman Michael C. Moffet, Commissioner Joseph F. Harkins, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

PENN VIRGINIA OIL & GAS CORPORATION  
2550 E STONE DR STE 110  
KINGSPORT, TN 37660-5863

April 27, 2009

Re: ODLE 23-12 #1  
API 15-017-20840-00-00  
23-21S-6E, 1980 FSL 660 FWL  
CHASE COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division has received your plugging proposal, form CP-1, for the above well and has reviewed the proposal for completeness. The central office will now forward your CP-1 to the district office listed below for review of the proposed plugging method. **Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113(b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit in accordance with K.A.R. 82-3-600.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. This notice in no way constitutes authorization to plug the above well by persons not having legal rights of ownership or interest in the well.

**This notice is void after October 24, 2009. The CP-1 filing does not bring the above well into compliance with K.A.R. 82-3-111 with regard to the Commission's temporary abandonment requirements.**

Sincerely,

Steve Bond  
Production Department Supervisor

District: #2  
3450 N. Rock Road, Suite 601  
Wichita, KS 67226  
(316) 630-4000