

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-095-21253-00-00
Spot: E2NE Sec/Twnshp/Rge: 31-28S-9W
1320 feet from N Section Line, 660 feet from E Section Line
Lease Name: ADELHARDT (CONRAD) Well #: 31-8
County: KINGMAN Total Vertical Depth: 2530 feet

Operator License No.: 5893
Op Name: PRATT WELL SERVICE, INC.
Address: PO BOX 847
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	2530	1092	100 SX
SURF	8.625	262		225 SX

82.23

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 03/09/2009 4:30 PM
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.
Proposal Rcvd. from: GARELD INSLEE Company: PRATT WELL SERVICE INC Phone: (620) 770-0995

Proposed Plugging Method: PER KCC RULES & REGULATIONS

Plugging Proposal Received By: DUANE KRUEGER WitnessType: PARTIAL
Date/Time Plugging Completed: 03/09/2009 4:30 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

TAGGED SANDED AT 2360' PLACED 4 SXS OF CEMENT ON TOP. BOND LOG SHOWED CEMENT ON BACK SIDE UP TO 1270'. SPOTTED 20 SXS OF CEMENT INSIDE CASING @ 1467'. SHOT CASING OFF AT 1092', PULLED CASING TO 930' SPOTTED 35 SXS OF CEMENT, PULLED CASING TO 318' CIRCULATED TO SURFACE WITH 135 SXS.

Perfs:

Top	Bot	Thru	Comments
2423	2429		

RECEIVED
DATE 4-27-09
TRV NO. 2009061462
RECEIVED
KANSAS CORPORATION COMMISSION
APR 10 2009

Remarks: BASIC ENERGY OUT OF PRATT, KS TICKET #19704

CONSERVATION DIVISION
WICHITA, KS

Plugged through: CSG

District: 02

Signed

(TECHNICIAN)

VJK