

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20556-00-01
Spot: NWNESW Sec/Twnshp/Rge: 14-27S-11W
2027 feet from S Section Line, 3367 feet from E Section Line
Lease Name: PARK Well #: 2
County: PRATT Total Vertical Depth: 4700 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4450		WITH 4 SX CMT
PROD	5.5	4570	1615	WITH 200 SX CMT
SURF	8.625	322		WITH 300 SX CMT

152.75

Well Type: SWD UIC Docket No: D25227.0 Date/Time to Plug: 03/12/2009 2:15 PM
Plug Co. License No.: 7023 Plug Co. Name: KLIMA WELL SERVICE, INC.
Proposal Rcvd. from: LANCE FELLHOELTER Company: TRANS PACIFIC Phone: (316) 262-3596

Proposed Plugging Method: CIBP @ 4450' & 4 SX CMT. LOAD HOLE WITH GEL. PLUG AT 1594' WITH 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 350' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/12/2009 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SET CIBP @ 4450' & PUT 4 SX CMT ON TOP OF CIBP THROUGH DUMP BAILER. LAID DOWN 5 1/2" CASING & RUN 2 7/8" TBG IN TO PLUG THROUGH. 1ST PLUG LOADED HOLE WITH GEL. PUMP 50 SX CMT AT 1594'. 2ND PLUG AT 660' WITH 50 SX CMT. 3RD PLUG AT 350' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4570	4700	OH	

INVOICED
DATE 4-27-09
INV NO 2009061469

KANSAS CORPORATION COMMISSION

APR 06 2009

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY BASIC ENERGY.

Plugged through: TBG

District: 01

RECEIVED

MAR 23 2009

KCC DODGE CITY

Signed

Stephen J. Pfeifer
(TECHNICIAN)

Form CP-278