

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-20682-00-00
Spot: W2NWSE Sec/Twnshp/Rge: 26-26S-15W
1980 feet from S Section Line, 2310 feet from E Section Line
Lease Name: LINCOLN LAND Well #: 3
County: PRATT Total Vertical Depth: 4454 feet

Operator License No.: 5141
Op Name: ZENITH DRILLING CORPORATION
Address: PO BOX 780428
WICHITA, KS 67278

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4453	2200	WITH 125 SX CMT
SURF	10.75	430		WITH 275 SX CMT

144.76

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 03/13/2009 1:30 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: PUMP 200# HULLS & 35 SX CMT. PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. PLUG AT 460' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 03/13/2009 2:30 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PUMPED DOWN 4 1/2" CASING WITH 200# HULLS & 35 SX CMT. PLUG THROUGH 4 1/2" CASING. 1ST PLUG AT 1000' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 460' WITH 70 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4375	4392		

INVOICED
DATE: 4-27-09
INV NO. 2009061470

KANSAS CORPORATION COMMISSION

APR 06 2009

RECEIVED

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

District: 01

RECEIVED
MAR 23 2009
KCC DODGE CITY

Signed Stephen J. Pfeifer
(TECHNICIAN)

Form CP 8/3

PKT