

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-063-21387-00-01
Spot: S2SEW Sec/Twnshp/Rge: 26-15S-30W
2979 feet from S Section Line, 3418 feet from E Section Line
Lease Name: L EVANS Well #: 1-26
County: GOVE Total Vertical Depth: 4400 feet

Operator License No.: 6170
Op Name: GLOBE OPERATING, INC.
Address: PO BOX 12
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comment
PC		2045		
PROD	5.5	4398	0	175 SX
SURF	8.625	344	0	190 SX

Well Type: SWD UIC Docket No: D26928.0 Date/Time to Plug: 04/08/2009 11:00 AM
Plug Co. License No.: 32970 Plug Co. Name: H-D OILFIELD SERVICE, INC.
Proposal Rcvd. from: RICHARD STALCUP Company: GLOBE OPERATING, INC. Phone: (620) 793-2891

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 600# hulls - 15 sxs gel.
Plug through casing.

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/08/2009 11:45 AM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

8 5/8" surface casing set at 344' w/190 sxs cement.
5 1/2" production casing set at 4398' w/175 sxs cement.
Port collar at 2045' w/425 sxs. PBTD 4070'.
Connected to 5 1/2" production casing - pumped 75 sxs cement with 400# hulls, followed with 15 sxs gel and 175 sxs cement mixed with 200# hulls.
Max. P.S.I. 1000#. S.I.P. 400#.
Connected to 8 5/8" surface casing. Pumped 10 sxs cement.
Max. P.S.I. 500#. S.I.P. 500#.

Perfs:

Top	Bot	Thru	Comments
3745	4010		

KANSAS CORPORATION COMMISSION
APR 13 2009
RECEIVED

INVOICED
DATE 4/29/09
INV. NO. 2009061474

Remarks: SWIFT SERVICES, INC.-TICKET #15793.

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

CM

Form CP-2/3

APR 08 2009

Replacement Card

WHITE & ELLIS / DAMAR RESOURCES
WICHITA KS 67201-8848

#1-26 EVANS, L.

26-15S-30W
2979'FSL & 3418'FEL, SEC
KANSAS

City: GOVE Spot: NE SW SE NW API 15-063-21387
Site: 8 N & 1/4 W OF HEALY KS Lat/Long: 38.72281 -100.62740
Field: SHARP NW EXT (1/8 N)
FR: 04/19/1991 Spd: 05/03/1991 Drig Cp: 05/12/1991 Issued: 07/01/1991 Revised: 09/22/2008

Copyright 2008 Independent Oil & Gas Service, Inc. Wichita, KS

Side 1

IP Status:
OIL, P 40 BO & 75 BWPD, LKC 3973-3976, 6/3/1991
Revisions: CORRECTION: 8/22/2008 - ORIG FR IN C
S/2 SE NW (CORR PER GPS)
Contr: WHITE & ELLIS
Geol: %THOMAS J. FUNK%
Elev: 2629 KB, 2624 GL, 2627 DF
Formation Tops: (L-Log, S-Sample, D-Driller)

L ANH	2037 +592
L B/ANH	2064 +565
L HEEB	3669 -1040
L LANS	3709 -1080
L MUN CR	3875 -1246
L STARK	3965 -1336
L PBTD	4050 -1421
L MARM	4079 -1450
L PAW	4171 -1542
L MYR STA	4207 -1578
L FT SC	4227 -1598

L CHER SH	4253 -1624
L JOHNSON ZN	4294 -1665
L MISS	4327 -1698
RTD	4400 -1771

Ceg: 8-5/8" 338 / 190 SX, 5-1/2" 4398 / 175 SX, PORT
COLLAR AT 2045 / 200 SX
Finds:
NO CORES
DST(1) 3716-3785 (LANS A,B) 30-45-45-60, 33Z
GIP, REC 104' GSY MCO (1% G, 60% OIL, 39% M),
61' GSY OCM (1% G, 30% OIL, 69% M), 61' GSY
OILY WCM (1% G, 9% OIL, 10% W, 80% M, CHL
40,000 PPM, MUD CHL 3000 PPM) ISIP 982# FSIP
970# IFP 24#-48# / FFP 75#-109#
DST(2) 3785-3814 (LANS E) 30-45-45-60, 150'
GIP, REC 30' CLEAN GSY OIL, 62' WOCM (35%
OIL, 5% W, 80% M), 62' OWCM (5% OIL, 45% W,
50% M, WTR CHL 50,000 PPM) ISIP 912# FSIP
888# IFP 24#-36# / FFP 48#-72#

Replacement Card

WHITE & ELLIS / DAMAR RESOURCES
WICHITA KS 67201-8848

#1-26 EVANS, L.

26-15S-30W
2979'FSL & 3418'FEL, SEC
KANSAS

Copyright 2008 Independent Oil & Gas Service, Inc. Wichita, KS

Side 2

DST(3) 3911-3960 (LANS I,J) 30-45-45-60, 228'
GIP, REC 20' OCM (20% OIL, 80% M), 62' GSY
OCM (15% G, 25% OIL, 60% M), 62' SLI WMCO
(60% OIL, 10% W, 30% M) ISIP 947# FSIP 947#
IFP 24#-36# / FFP 48#-60#
DST(4) 3966-3985 (LANS K) 30-45-45-60, SB,
1612' GIP, REC 495' CLEAN GSY OIL, 90' GSY
MCO (20% G, 79% OIL, 1% M) ISIP 771# FSIP
771# IFP 48#-109# / FFP 133#-228#
DST(5) 4002-4022 (MID CR) 30-45-45-60, 484'
GIP, REC 68' CLEAN GSY OIL, 62' GSY OCM (15%
G, 35% OIL, 50% M) ISIP 133# FSIP 169# IFP
12#-24# / FFP 24#-36#
DST(6) 4255-4315 (JOHNSON ZN) 30-30-30-30,
REC 20' SLI OCM (1% OIL, 99% M) ISIP 771# FSIP
654# IFP 12#-12# / FFP 12#-12#
Comp Info: TRGT ZN: LKC, MISS, PTD 4350 (MISS),
MICT - CO, PF (MARM) 4080-4084, W / 3 SPF, AC
250 GAL (15% MCA), NON-COMMERCIAL, PF
(PLEAS) 4060-4062, W / 3 SPF, AC 250 GAL (15%
MCA), NON-COMMERCIAL, PF (LANS K) 3973-3976,
W / 3 SPF, AC 250 GAL (15% MCA), SO, SET 2-7/8"
TBG AT 3950, POP, P 40 BO & 75 BWPD 6/3/1991 -
(APPL TO P & A FILED 8/2008)