

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-167-23566-00-00
Spot: N2SW Sec/Twnshp/Rge: 3-11S-13W
1908 feet from S Section Line, 1439 feet from W Section Line
Lease Name: BROWN "A" Well #: 1-3
County: RUSSELL Total Vertical Depth: 3625 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	436		

117.81

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 04/09/2009 12:00 AM
Plug Co. License No.: 33350 Plug Co. Name: SOUTHWIND DRILLING, INC.
Proposal Rcvd. from: JAY KRIER Company: TRANS PACIFIC OIL CORPORATIO Phone: (316) 262-3596

Proposed Plugging Method: Ordered 155 sxs 60/40 pozmix - 4% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: PAT STAAB WitnessType: NONE
Date/Time Plugging Completed: 04/09/2009 12:15 AM KCC Agent: PAT STAAB

Actual Plugging Report:

1st. Plug at 820' w/25 sxs.
2nd. Plug at 696' w/50 sxs.
3rd. Plug at 486' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 30 sxs.

Perfs:

INVOICED
DATE: 4/29/09
INV. NO. 2009061476

STATE CORPORATION COMMISSION
APR 13 2009
RECEIVED

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed [Signature]
(TECHNICIAN) CM

APR 09 2009

PKT