

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-009-04917-00-00  
Spot: SWSWNE Sec/Twnshp/Rge: 21-20S-12W  
2970 feet from S Section Line, 2310 feet from E Section Line  
Lease Name: HULME B Well #: 2  
County: BARTON Total Vertical Depth: 3505 feet

Operator License No.: 3273  
Op Name: LOEB, HERMAN L.  
Address: PO BOX 524  
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3504	0	w/unknown sxs cmt
SURF	8.625	237	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/01/2009 9:00 AM  
Plug Co. License No.: 5893 Plug Co. Name: PRATT WELL SERVICE, INC.  
Proposal Rcvd. from: GEORGE PAYNE Company: LOEB, HERMAN L. Phone: (618) 943-2227

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 11 sxs gel.  
Perfed at 1400' - 650' - 150'.

113.91

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/03/2009 12:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

04/01/2009 - Ran tubing to 3308' - pumped 11 sxs gel - pumped 75 sxs cement.  
Pulled tubing - shut down.  
04/03/2009 - Ran tubing to 1400' - pumped 125 sxs cement - circulated out 5 1/2" - shut in.  
Pumped 50 sxs out backside - shut down - pulled tubing.  
Tied to casing - pumped 25 sxs cement.  
Shut in. Backside squeezed. Max. P.S.I. 300#. Shut in.

Perfs:

INVOICED  
DATE 4-29-09  
INV. NO. 2009061482

STATE CORPORATION COMMISSION  
APR 13 2009  
RECEIVED

Remarks: ALLIED CEMENTING COMPANY-TICKET #37437.

Plugged through: CSG

District: 04

Signed Bruce Rodie  
(TECHNICIAN)

CM

Form CP-2/3

APR 07 2009

PKY

HONAKER-DAVIS DRLG

#2 HULME 'B'

21-20-12W  
SW SW NE 53

Contr. HONAKER-DAVIS DRLG

BARTON

County

E. 1852

Comm. 1-25-57

Comp. 4-12-57

IP 440 BOPD/ARB  
PHY POT

Tops	Depth	Datum
Ann	± 650	
HEEB	3030	-1178
BR LM	3161	-1309
KC	3175	-1323
ARB	3408	-1556
ID	3505	-1653

Casing

8" 237

5" 3504

DST 3185-3214/1 HR, G/6"

132 MCFG, 1230' 0, BHP 840#

DST 3295-3316/20", 3' MUD,

BHP 100#

PERF 12/3451-53: SWB 18 BOPH

WORKMAN NW POOL-

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE  
WICHITA, KANSAS