

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-21408-00-00
Spot: NESESW Sec/Twnshp/Rge: 19-7S-17W
990 feet from S Section Line, 2310 feet from W Section Line
Lease Name: F WALKER Well #: 2
County: ROOKS Total Vertical Depth: 3267 feet

Operator License No.: 3273
Op Name: LOEB, HERMAN L.
Address: PO BOX 524
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
COND	12.75	92		
PROD	5.5	3226	0	w/unknown sxs cmt
SURF	8.625	1141	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/08/2009 10:00 AM
Plug Co. License No.: 34093 Plug Co. Name: SUMMIT WELL SERVICE LLC
Proposal Rcvd. from: _____ Company: LOEB, HERMAN L. Phone: (618) 943-2227

Proposed Plugging Method: Ordered 450 sxs 60/40 pozmix - 4% gel - 400# hulls.
CIBP at 3196'. Perf shot at 1100'.

106.18

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/08/2009 3:00 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 2800' - pumped 16 sxs gel - followed with 50 sxs cement with 200# hulls.
Pulled tubing to 1133' - pumped 105 sxs cement - good circulation.
Pulled tubing out - tied onto 5 1/2" - squeezed with 30 sxs cement.
S.I.P. 300#. Can not tie onto backside - cut surface pipe off - backside full of cement.

Perfs:

Top	Bot	Thru	Comments
2940	3140		

INVOICED
DATE: 4-29-09
INV NO: 2009061482
KANSAS CORPORATION COMMISSION
APR 13 2009

Remarks: ALLIED CEMENTING COMPANY-TICKET 37501.

Plugged through: TBG

District: 04

Signed [Signature]
(TECHNICIAN)

CM

Form CP-2/3

APR 09 2009

PKT

