

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-04919-00-00
Spot: NESWNE Sec/Twnshp/Rge: 21-20S-12W
3630 feet from S Section Line, 1650 feet from E Section Line
Lease Name: HULME B Well #: 5
County: BARTON Total Vertical Depth: 3475 feet

Operator License No.: 3273
Op Name: LOEB, HERMAN L.

Address: PO BOX 524
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3473	0	w/unknown sxs cmt
SURF	8.625	243	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/01/2009 1:00 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: GEORGE PAYNE Company: LOEB, HERMAN L. Phone: (618) 943-2227

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 10 sxs gel.
Perfed at 1400' - 650' - 150'.

112.94

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/03/2009 3:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

04/01/2009 - Set CBIP at 3360'.
Ran tubing to 3350' - pumped 10 sxs gel - pumped 25 sxs cement.
Pulled tubing - shut down.
04/03/2009 - Ran tubing to 1400' - pumped 125 sxs cement - circulated out 5 1/2" - shut in -
cement circulated out backside.
Pulled tubing - tied to casing - pumped 30 sxs cement - cement circulated out backside.
Max. P.S.I. 300#. Shut in.

Perfs:

INVOICED
DATE 4-29-09
INV. NO 2009061482

KANSAS CORPORATION COMMISSION
APR 13 2009
RECEIVED

Remarks: ALLIED CEMENTING COMPANY-TICKET #37438.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

CM

Form CP-2/3

APR 07 2009

PKT

HONAKER-DAVIS DRLG #5 HULME 'B' 21-20-12W NE SW NE 53

Contr. HONAKER-DAVIS DRLG BARTON County

E. 1836 Comm. 8-19-57 Comp. 9-20-57 IP 202 BOPD/ARB
PHY POT

Tops	Depth	Datum
HEEB	3012	-1176
BR 1 M	3133	-1297
KG	3150	-1314
ARB	3383	-1547
TD	3475	-1639

Casing
 8" 243
 5" 3473
 DST 3151-74, G/2", 1930 MCFG
 90' GCM, BHP 1128#
 DST 3274-94/1 HR, 61' HO &
 GCM, BHP 450#
 PERF 3430-36: SWB 10 BOPH,
 NW

WORKMAN NW POOL

+	+	+
+	+	+
+	+	+

INDEPENDENT OIL & GAS SERVICE
 WICHITA, KANSAS