

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-009-23099-00-00
Spot: NWSEW Sec/Twnshp/Rge: 10-16S-15W
3630 feet from S Section Line, 3630 feet from E Section Line
Lease Name: KEIL Well #: 2-A
County: BARTON Total Vertical Depth: 3495 feet

Operator License No.: 4952
Op Name: SCHLOBOHM, STARR F.
Address: 10 GREENLEAF DR
WOLFEBORO, NH 03894

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3494	0	w/unknown sxs cmt
SURF	8.625	359	0	w/unknown sxs cmt

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/07/2009 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: JOHN DRISCOLL Company: SCHLOBOHM, STARR F. Phone: (603) 569-9790

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 4% gel - 300# hulls
Emergency plug rig over hole.
Mill and reamer stuck at 1200'. Mill stuck at 685'.
113.59

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 04/07/2009 1:00 PM KCC Agent: BRUCE RODIE

Actual Plugging Report:

Tied to tubing with mill on end at 685' - pumped 175 sxs cement - circulated cement to surface. Unscrewed from mill - pulled 5 joints tubing - tied to casing - pumped 75 sxs cement with 250# hulls.
Max. P.S.I. 600#. Shut in.
Tied to backside - pumped 25 sxs cement.
Max. P.S.I. 500#. Shut in.

Perfs:

INVOICED
DATE 4-29-09
INV. NO. 2009061484

KANSAS CORPORATION COMMISSION
APR 30 2009
RECEIVED

Remarks: ALLIED CEMENTING COMPANY-TICKET #37500.

Plugged through: CSG

District: 04

Signed Bruce Rodie
(TECHNICIAN)

cm

PKT

YOST OIL OPERATIONS
BOX 811

REPLACEMENT CARD


10-16-15W
NW SE NW

#2 "A" KEIL

RUSSELL, KS 67665

CONTR BIG THREE DRLG. CO., INC. CTY BARTON

GEOL _____ FIELD GALATIA WEST



ELV 1975 KB SPD 5/10/83 CARD ISSUED 8/18/83 IP P 65 BOPD
LKC 3394-3400

API 15-009-23,099

LOG	Tops	Depth Datum
ANH	1004 +	971
B/ ANH	1034 +	941
GR HAV	2588-	613
TARK	2659-	684
TOP	2926-	951
HEEB	3155-	1180
TOR	3173-	1198
DOUG	3188-	1213
LANS	3214-	1239
BKC	3442-	1467
PENN CONG	3458-	1483
RTD	3495-	1520

8 5.8 " 359.5 12 " 3494

DST (1) 3346-66 (LANS) 45-45-45, 2445' GIP, REC 165' G & O SPTD M, 240' OIL, 60' G & MCO, 60' G & OCM, SIP 498-4843, FP 187-197 217-227#, HP 1933-1933#
MCT - CO, PF (PENN) 3452-57, AC 250G, SWB DWN, REC WTR, SET BP AT 3450, PF (LKC) 3418-23, AC 250G, SWB LD & WTR, SET BP AT 3415, PF (LKC) 3394-3400, AC 500G, SWB LD & GSO, POP, P 65 BOPD (GR 47.9'), 6 1 83

CORRECTION: 9/8/83 - WAS LANS 3241-1266

COPYRIGHT 1983
INDEPENDENT OIL & GAS SERVICE, INC.
WICHITA, KANSAS