

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-195-21916-00-00  
Spot: SWSENE Sec/Twnshp/Rge: 10-11S-23W  
2970 feet from S Section Line, 990 feet from E Section Line  
Lease Name: DENISON Well #: 1  
County: TREGO Total Vertical Depth: 3870 feet

Operator License No.: 5184  
Op Name: SHIELDS OIL PRODUCERS INC  
Address: 326 N MAIN  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3765	0	w/450 sxs cmt
SURF	8.625	218	0	w/160 sxs cmt

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 04/09/2009 9:00 AM  
Plug Co. License No.: 5184 Plug Co. Name: SHIELDS OIL PRODUCERS INC  
Proposal Rcvd. from: MICHAEL A MCGLOCKLIN Company: SHIELDS OIL PRODUCERS INC Phone: (785) 483-3141

Proposed Plugging Method: Ordered 350 sxs 60/40 pozmix - 4% gel - 400# hulls.  
BPTD 3748'. Fluid level was 120' off bottom - very low fluid level.

125.78

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 04/09/2009 9:45 AM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Tied onto casing - pumped 260 sxs cement with 400# hulls.  
Shut in 300#. Casing full.  
Tied onto backside - pumped 10 sxs cement.  
Shut in 300#.

Perfs:

Top	Bot	Thru	Comments
3674	3680		

INVOICED  
DATE: 4-29-09  
INV. NO. 2009061485  
KANSAS CORPORATION COMMISSION  
APR 13 2009  
RECEIVED

Remarks: ALLIED CEMENTING COMPANY-TICKET #35038.

Plugged through: CSG

District: 04

Signed [Signature]  
(TECHNICIAN)

CM

PKT

#1 DENISON

site: 5 N & 3/4 E OF WAKEENEY, KS.      city: TREGO      API 15-195-21916  
 contr: SHIELDS DRILLING      field: WAKEENEY  
 geol: GERALD HONAS  
 fr date 05/20/87      spd date 06/22/87      drig comp 07/01/87      card issued 08/12/87      last revised 08/12/87


Elv: 2254 KB LOG

tops .....	depth/datum
ANH.....	1716 +538
B/ANH.....	1760 +494
TOP.....	3240 -986
HEEB.....	3258 -1004
TOR.....	3479 -1225
LANS.....	3494 -1240
BKC.....	3719 -1465
MARM.....	3822 -1568
PBD.....	3748 -1494
RTD.....	3870 -1616

**IP status:**  
 OIL, P 40 BO & 10 BWPD, LKC 3674-3680 ,  
 CSG: 8-5/8" 218 / 160 SX, 4-1/2" 3765 / 450 SX  
 NO CORES  
 DST (1) 3455-3503 (TOR, LKC), / 30-30-30-45, 30' GIP,  
 REC 925' GSY MW ISIP 916# FSIP 916# IFP 117#  
 -302# FFP 360# -469# IHP 1818# FHP 1798#

NOTE: CORRECTION: 8/12/87 - ORIGINALLY FIRST  
 REPORTED AS MCNAMES & PATTERSON AS OPERATOR,  
 OPERATIONS TURNED OVER TO SHIELDS OIL AT CSG  
 POINT

(over)