

15-051-20704-00-00

Form CP-3
Rev. 6-4-68

KANSAS

Y

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
12-28-1970
DEC 28 1970
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Jet Drilling Company Inc.

Complete Address 511 One Twenty Bldg., Wichita, Kansas

Lease Name Christine Pulec Well No. 1

Location NW NW NW Sec. 8 Twp. 11 Rge. (E) (W) 19

County Ellis Total Depth 3708'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated

Plugging Contractor Murfin Drlg.

Address Wichita, Kansas License No.

Operation Completed: Hour 4:15 A Day 23 Month 12 Year 1970

The above well was plugged as follows:

RTD 3708' 8 5/8 csg set at 242' cwc Cmt. Mat. 50-50 poz W/6% gel.

Gunned pits, circulated heavy mud, set cementing plug at 660' and displaced 70 sk

cmt thru drill pipe. Heavy mud to 220' set cementing plug and displaced 20 sk cmt

thru drill pipe. Heavy mud to 140' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 12/28/70
INV. NO. 3123-W

Signed: Leo J. Massey
Well Plugging Supervisor