



STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
11-4-74  
NOV 4 1974  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Abercrombie Drilling, Incorporated,

Complete Address 801 Union Center, Wichita, Kansas.

Lease Name Mosier Well No. 1

Location CSW-SW-SW Sec. 3 Twp. 9 Rge. (E) (W) 27

County Sheridan Total Depth 4010'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 6:30 AM Day 26 Month 10 Year 1974

The above well was plugged as follows:

236'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1075'

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 110 Cu. Ft. cement  
thru DP from 1300' to 975'. Pulled DP to 245' and displaced 30 Cu. Ft. cement thru  
DP from 245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED  
DATE 11/4/74  
INV. NO. 244-w