

KANSAS



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
6-18-70
JUN 18 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name American Drilling Corporation,

Complete Address 360 Sutton Place, Wichita, Kansas.

Lease Name Ochs Well No. 1

Location NE-NW-NW Sec. 24 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4167

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Forbes Casing Pulling Company, Incorporated,

Address Box #211, Great Bend, Kansas. License No. 49

Operation Completed: Hour 12:00 M Day 11 Month 6 Year 1970

The above well was plugged as follows:

280'--8 5/8" Surface casing, cement circulated with 200 Sx.
4163'--4 1/2" Production casing cemented on bottom with 150 Sx. No plug back indicated,
Top perforations from 3908' to 3914'.

Pushed plug to 3875', built sand bridge from 3875' to 3850' and set 3 Sx. cement with
dump bailer. Pulled 4 1/2" casing and squeezed well initially with 5 sacks hulls and 8
sacks gel and followed with 100 Sx. cement from 1500' to 1175' then 21 sacks gel from
1175' to 325' and followed with 25 Sx. cement from 325' to 250' then 6 sacks gel from
250' to 30' and finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in
pressure-250#. Final shut-in pressure-100#. (Mudding and cementing by Allied Cementing).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols
Well Plugging Supervisor

INVOICED

DATE 6/18/70

INV. NO. 2070-W