

15-179-20345-0000

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
SEP 17 1974
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Zenith Drilling Corporation,
Complete Address Suite 600, 200 West Douglas, Wichita, Kansas.
Lease Name Ochs Well No. 2
Location SE-SW-NE Sec. 24 Twp. 9 Rge. (E) (W) 28
County Sheridan Total Depth 4155'
Abandoned Oil Well Gas Well Input Well SWD Well D & A X
Other well as hereafter indicated
Plugging Contractor Muhfin Drilling Company,
Address 617 Union Center, Wichita, Ks. License No.
Operation Completed: Hour 1:30 PM Day 12 Month 9 Year 1974

The above well was plugged as follows:

253'--8 5/8" Surface casing, cement circulated with 150 Sx.
Top of Dakota section @ 1225'.
Circulated hole with heavy mud. Pulled DP to 1450' and displaced 110 Cu. Ft. cement
thru DP from 1450' to 1125'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
ement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: M. L. Dechick
Well Plugging Supervisor

INVOICED

DATE 9/18/74
INV. NO. 9902-W