

KANSAS

*Y*  
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 4 - 1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name L. G. Stephenson,

Complete Address 360 Sutton Place, Wichita, Kansas.

Lease Name Ochs Well No. 3

Location SW-NE-NE Sec. 24 Twp. 9 Rge. (E) (W)28

County Sheridan Total Depth 4130'

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Red Tiger Drilling Company,

Address 1720 Wichita Plaza, Wichita, Kansas. License No. \_\_\_\_\_

Operation Completed: Hour 3:30 PM Day 1 Month 12 Year 1972

The above well was plugged as follows:

266'--8 5/8" Surface casing, cement circulated with 185 Sx.  
Top of Dakota section @ 1150'.

Circulated hole with heavy mud. Pulled DP to 1375' and displaced 110 Cu. Ft. cement  
thru DP from 1375' to 1050'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 12/5/72  
INV. NO. 6688-W

Signed: M. L. Nichols  
Well Plugging Supervisor