

15-179-20392-0000

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT RECEIVED  
STATE CORPORATION COMMISSION

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

9-27-74  
SEP 27 1974

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Zenith Drilling Corporation,  
Complete Address Suite 600, 200 West Douglas, Wichita, Kansas.  
Lease Name Haffner Well No. 2  
Location SW-SW-NW Sec. 19 Twp. 9 Rge. (E) (W) 27  
County Sheridan Total Depth 4135'  
Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A X  
Other well as hereafter indicated \_\_\_\_\_  
Plugging Contractor Murfin Drilling Company,  
Address 617 Union Center, Wichita, Kansas. License No. \_\_\_\_\_  
Operation Completed: Hour 6:30 PM Day 21 Month 9 Year 1974

The above well was plugged as follows:

260'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1175'.  
Circulated hole with heavy mud. Pulled DP to 1400' and displaced 110 Cu. Ft. cement  
thru DP from 1400' to 1075'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru  
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: N. L. Nichols  
Well Plugging Supervisor

INVOICED  
DATE 9/27/74  
INV. NO. 9965-4