

15-179-19031-0000

Form CP-3
Rev. 6-26-62

4
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
JUL 11 1968
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name M. J. Bove Operating Company,

Complete Address: 754 E. Wichita Avenue, Russell, Kansas.

Lease Name Richards Well No. 2

Location W2 SW-SE-NW Sec. 17 Twp. 9 Rge. (E) (W) 26

County Sheridan Total Depth 4060'

Abandoned Oil Well X Gas Well Input Well X SWD Well D & A
RT KCC

Other well as hereafter indicated:

Plugging Contractor: Allied Cementing Company, Incorporated,

Address: Box #207, Russell, Kansas. License No.

Operation Completed: Hour 12:20PM Day 5 Month 7 Year 1968

The Above well was plugged as follows:

308'--8 5/8" Surface pipe, cement circulated.
4059'--5 1/2" Production casing cemented with 150 Sx. Top perforations @ 3880'.

Pushed plug to 3500' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and
squeezed well initially with 5 sacks huils and 4 sacks gel then 100 Sx. cement from
1375' to 1050' then 20 sacks gel from 1050' to 325' and followed with 20 Sx. cement
from 325' to 265' then 6 sacks gel from 265' to 30' and finally 10 Sx. cement from
30' to bottom of cellar. Maximum pump-in pressure-100#. Final shut-in pressure-100#.

I hereby certify that the above well was plugged as herein stated

Signed: *M. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 7/12/68
INV. NO. 8086-W