

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
6-25-70
JUN 25 1970
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address 905 Century Plaza, Wichita, Kansas.

Lease Name Shaw Well No. 3

Location SW-SW-SE Sec. 7 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4169'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 5:00 PM Day 23 Month 6 Year 1970

The above well was plugged as follows:

217'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1225'.

Circulated hole with heavy mud. Pulled DP to 1425' and displaced 100 Sx. cement thru
DP from 1425 to 1100'. Pulled DP to 245' and displaced 25 Sx. cement thru DP from
245' to 170'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: M. L. Nichols
Well Plugging Supervisor

DATE 6/25/70
INV. NO. 2120-u