

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
8-18-69  
AUG 18 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Chief Drilling Company, Incorporated,

Complete Address Suite #905, Wichita, Kansas,

Lease Name Mosier Well No. 2

Location 150' SW of SE-SW Sec. 6 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4075'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Above

Address        License No.       

Operation Completed: Hour 11:00 AM Day 16 Month 8 Year 1969

The above well was plugged as follows:

218'--8 5/8" Surface casing, cement circulated with 170 Sx.  
Top of Dakota section @ 1175'.

Circulated hole with heavy mud. Pulled DP to 1400' and displaced 100 Sx. cement thru  
DP from 1400' to 1075'. Pulled DP to 185' and displaced 20 Sx. cement thru DP from  
185' to 125'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to  
bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 8-18-69

INV. NO. 328-W

Signed: M. L. Fickel  
Well Plugging Supervisor