

KANSAS

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT
RECEIVED
8-27-73
AUG 27 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Rains & Williamson Oil Company, Incorporated,

Complete Address 435 Page Court, Wichita, Kansas.

Lease Name Shaw Well No. 1

Location NE-SE-NE Sec. 7 Twp. 9 Rge. (E) (W)28

County Sheridan Total Depth 4180'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Above

Address License No.

Operation Completed: Hour 2:00 AM Day 23 Month 8 Year 1973

The above well was plugged as follows:

284'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 1175'.

Circulated hole with heavy mud. Pulled DP to 1400' and displaced 110 Cu. Ft. cement
thru DP from 1400' to 1075'. Pulled DP to 300' and displaced 30 Cu. Ft. cement thru
DP from 300' to 225'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 8/30/73
INV. NO. 7826-W

Signed: H. L. Nichols
Well Plugging Supervisor