

15-179-05643-00-00²

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

RECEIVED
STATE CORPORATION COMMISSION
1-2-69
JAN 2 1969
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name M. J. Bove Operations,

Complete Address: 754 East Wichita Avenue, Russell, Kansas.

Lease Name Richards Well No. 1

Location NE-NE-NW Sec. 17 Twp. 9 Rge. (E) (W) 26

County Sheridan Total Depth 4050'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Allied Cementing Company, Incorporated,

Address: Box #207, Russell, Kansas. License No. _____

Operation Completed: Hour 2:00 PM Day 30 Month 12 Year 1968

The Above well was plugged as follows:

304'--8 5/8" Surface casing, cement circulated.
4050'--5 1/2" Production casing cemented on bottom with 150 Sx. Well plugged back to
4037'. Top perforations @ 3874'.

Sanded well back to 3850' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing
and squeezed well initially with 11 sacks gel plus 5 sacks hulls and followed with 100
Sx. cement from 1150' to 825' then 13 sacks gel from 825' to 325' and followed with 20
Sx. cement from 325' to 265' then 6 sacks gel from 265' to 30' and finally 10 Sx.
cement from 30' to bottom of cellar. Maximum pump-in pressure--300#. Final shut-in
pressure--150#. (Mudding and cementing operations performed by Allied Cementing Co.).

I hereby certify that the above well was plugged as herein stated.

Signed: M. S. Nichols
Well Plugging Supervisor

INVOICED

DATE 1-2-69

INV. NO. 9133-W