

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

RECEIVED
STATE CORPORATION COMMISSION
12-13-74
DEC 13 1974
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Chief Drilling Company Inc.

Complete Address 905 Century Plaza, Suite 905, Wichita, Kansas 67202

Lease Name Shaw Well No. 4

Location SE NW SW Sec. 7 Twp. 9 Rge. (E) (W) 28

County Sheridan Total Depth 4086'

Abandoned Oil Well XX Gas Well Input Well SWD Well D & A

Other well as hereafter indicated

Plugging Contractor Kelso Casing Pulling

Address Box 176, Chase, Kansas 67524 License No. 683

Operation Completed: Hour 1 P Day 11 Month 12 Year 1974

The above well was plugged as follows:

Total Depth 4086' 8 5/8 csg set at 215' cwc 160 sk.

5 1/2 csg set at 4085' cw 175 sk cement. (PFS 4019')

Set 5 1/2 wood plug at 3900' -poured 50' sd -dumped 5 sk cem W/dump bailer. (3900-3915)

Cutoff & recovered 1508' of 5 1/2 csg.

Pumped down 8 5/8 csg with 20 sk gel & water W/300 lbs hulls -70 sk cem. -15 sx gel & water, released 8 5/8 plug & pumped 50 sk cam. by Allied.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 12/16/74

INV. NO. 471-W

Signed: Leo P. Massey
Well Plugging Supervisor