



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 11 1968

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name M. J. Bove Operating Company,

Complete Address: 75 1/2 E. Wichita Avenue, Russell, Kansas.

Lease Name Richards Well No. 11

Location CN/2-SE-NW Sec. 17 Twp. 9 Rge. (E) (W) 26

County Sheridan Total Depth 1060'

Abandoned Oil Well Gas Well Input Well SWD Well D & A
RTKCC

Other well as hereafter indicated: _____

Plugging Contractor: Allied Cementing Company, Incorporated,

Address: Box #207, Russell, Kansas. License No. _____

Operation Completed: Hour 2:15 PM Day 5 Month 7 Year 1968

The Above well was plugged as follows:

300'--8 5/8" Surface pipe, cement circulated.
1060'--5 1/4" casing cemented on bottom with 150 Sx. Top perforations @ 3886.

Pushed Plug to 3750' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing and
squeezed well initially with 5 sacks hulls and 4 sacks gel then 100 Sx. cement from
1375' to 1050' then 20 sacks gel from 1050 to 325' and followed with 20 Sx. cement
from 325' to 265' then 6 sacks gel from 265' to 30' and finally 10 Sx. cement from
30' to bottom of cellar. Maximum pump-in pressure-100#. Final shut-in pressure-100#.

I hereby certify that the above well was plugged as herein stated.

Signed: *H. A. Nichols*
Well Plugging Supervisor

INVOICED

DATE 7/12/68

INV. NO. 8087-w