

15-179. 20344-0000

Form CP-3
Rev. 6-4-68

KANSAS

10
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
7-6-73
JUL 6 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Zenith Drilling Corporation, Inc.,

Complete Address 200 West Douglas, Wichita, Kansas.

Lease Name Haffner Well No. B-1

Location CNW-SW Sec. 19 Twp. 9 Rge. (E) (W) 27

County Sheridan Total Depth 4150'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated

Plugging Contractor Murfin Drilling Company,

Address 617 Union Center, Wichita, Kansas. License No.

Operation Completed: Hour 12:00 PM Day 3 Month 7 Year 1973

The above well was plugged as follows:

260'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1250'.

Circulated hole with heavy mud. Pulled DP to 1475' and displaced 110 Cu. Ft. cement
thru DP from 1475' to 1150'. Pulled DP to 275' and displaced 30 Cu. Ft. cement thru
DP from 275' to 200'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: *R. L. Nichols*
Well Plugging Supervisor

INVOICED
DATE 7/6/73
INV. NO. 7604-W