

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
3-22-74  
MAR 22 1974  
CONSERVATION DIVISION  
WICHITA, KANSAS

Operator's Full Name Beren Corporation.

Complete Address 1130 Vickers KSB&T Building, Wichita, Kansas.

Lease Name Mills Well No. 1

Location NW-SW-SE Sec. 17 Twp. 9 Rge. (E) (W) 26

County Sheridan Total Depth 4050'

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A X

Other well as hereafter indicated       

Plugging Contractor Red Tiger Drilling Company.

Address 1720 Wichita Plaza, Wichita, Kans. License No.       

Operation Completed: Hour 2:30 PM Day 20 Month 3 Year 1974

The above well was plugged as follows:

301'--8 5/8" Surface casing, cement circulated.  
top of Dakota section @ 1075'.

Circulated hole with heavy mud. Pulled DP to 1300' and displaced 110 Cu. Ft. cement  
thru DP from 1300' to 975'. Pulled DP to 310' and displaced 30 Cu. Ft. cement thru  
DP from 310' to 235'. Pulled DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft.  
cement to bottom of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 3/22/74  
INV. NO. 8785-W

Signed: A. L. Nichols  
Well Plugging Supervisor