

15-179-05603-00-00  
Form CP-3  
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
1-2-69  
JAN 2 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name M. J. Bove Operations,

Complete Address: 75 1/2 East Wichita Avenue, Russell, Kansas.

Lease Name Richards Well No. 3

Location W/2-NE-NW Sec. 17 Twp. 9 Rge. (E) (W) 26

County Sheridan Total Depth 4060'

Abandoned Oil Well X Gas Well        Input Well        SWD Well        D & A       

Other well as hereafter indicated:       

Plugging Contractor: Allied Cementing Company, Incorporated,

Address: Box #207, Russell, Kansas. License No.       

Operation Completed: Hour 3:30 PM Day 30 Month 12 Year 1968

The Above well was plugged as follows:

309'--8 5/8" Surface casing, cement circulated.  
4030'--5 1/2" Production casing cemented on bottom with 150 Sx. Top perforations @ 3863'.

Sanded well back to 3800' and set 5 Sx. cement with dump bailer. Pulled 5 1/2" casing  
and squeezed well initially with 11 sacks gel and 5 sacks hulls and followed with  
100 Sx. cement from 1150' to 825' then 13 sacks gel from 825 to 325' and followed  
with 20 Sx. cement from 325' to 265' then 6 sacks gel from 265' to 30' and finally  
10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure--250#. Final  
shut-in pressure--100#. (Mudding and cementing operations performed by Allied Cementing).

I hereby certify that the above well was plugged as herein stated.

Signed: W. L. Nichols  
Well Plugging Supervisor

INVOICED  
DATE 1-2-69  
INV. NO. 9132-W