

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
5-13-63  
MAY 13 1963

Operator's Full Name C & G Drilling Company, CONSERVATION DIVISION  
Wichita, Kansas  
Complete Address: 107 Rule Building, Wichita, Kansas.  
Lease Name Corke Well No. 1  
Location CNW-NW Sec. 24 Twp. 9 Rge. (E) (W) 26  
County Sheridan Total Depth 4170  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Pipe Pullers Incorporated  
Address: 1809 Lakin, Great Bend, Kansas. License No. 462  
Operation Completed: Hour 10:00AM Day 9 Month 5 Year 1963

The Above well was plugged as follows:

239' 8 5/8" surface pipe, cement circulated w/150 Sx.  
4168' 5 1/2", cemented w/ 100 Sx. Well plugged back to 4140'. Top per-  
foration @ 4063'.  
Sanded well back to 3900', set plug and 10' bridge and 5 Sx cement with  
dump bailer. Pulled 5 1/2" to 550', circulated heavy gel mud, (25 Sx Gel)  
and displaced 20 Sx cement thru 5 1/2". Pulled 5 1/2" to 210' and displaced  
20 Sx cement thru 5 1/2". Pulled 5 1/2", set bridge @ 35' and 10 Sx cement  
to bottom of cellar.

(Mudding and cementing operations performed by Globe Cementing Co.)

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 5/13/63  
INV. NO. 4060-W

Signed: N. L. Fichel  
Well Plugging Supervisor