



KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
11-18-68
NOV 18 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Okmar Oil Company,

Complete Address: 1130 Wichita Plaza Building, Wichita, Kansas.

Lease Name Corke Well No. 1

Location SE-SE-SE Sec. 24 Twp. 9 Rge. (E) (W) 26

County Sheridan Total Depth 4130

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Company, Incorporated,

Address: Box #364, Great Bend, Kansas. License No. 9

Operation Completed: Hour 11:30AM Day 12 Month 11 Year 1968

The Above well was plugged as follows:

227'--8 5/8" Surface casing, cement circulated. (6 1/4" Hole).
4129'--4 1/2" Production casing cemented on bottom with 100 Sx. No plug back indicated.
Top perforations @ 4064'.

Sand well back to 4050' and set 3 Sx. cement with dump bailer. Pulled 4 1/2" casing and
Squeezed well with initially 11 sacks gel plus 3 sacks hulls in initial gel and foll-
owed with 70 Sx. cement from 1150' to 820' then 7 sacks gel from 820' to 220' and
followed with 20 Sx. cement from 220' to 160' then sacks gel from 160' to 30' and
finally 10 Sx. cement from 30' to bottom of cellar. Maximum pump-in pressure-100#.
Final shut-in pressure-50#.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: N. L. Nichols
Well Plugging Supervisor

DATE 11/18/68
INV. NO. 8831-W