

State of Kansas



ROBERT B. DOCKING Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 DALE E. SAFFELS Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 1 1 1968
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Preston Burkey of M. J. Bove Operating Co., has this date requested permission to plug the following described well:

Mr. Burkey guarantees payment of the plugging fee.

Operator's full Name: M. J. Bove Operating Company.

Complete Address: 754 E. Wichita Ave., Russell, Kansas.

Lease Name: Richards Well No. 2

Location: W2^{ET} SW-SE-NW Sec. 17 Twp. 9 Rge. (E)(W) 26

County: Sheridan Total Depth 4060 Oil Well X

Gas Well Input Well X SWD Well D & A Lost Hole

Mr. Burkey was instructed to plug the well as follows:

308'--8 5/8" Surface pipe, cement circulated.
4059' 5 1/2" Production casing cemented with 150 Sx. Top perforations @ 3880'.

Push plug to 3500' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 30 sacks gel plus 5 sacks hulls and 130 Sx. cement staged.

Very truly yours,

Conservation Division Agent