



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION
 1-2-69
 JAN 2 1969
 CONSERVATION DIVISION
 Wichita, Kansas

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Preston Burkey of M. J. Bove Operations has this date requested permission to plug the following described well:

Mr. Burkey guarantees payment of the plugging fee.

Operator's full Name: M. J. Bove Operations,

Complete Address: 754 East Wichita Avenue, Russell, Kansas.

Lease Name: Richards Well No. 3

Location: W/2-NE-NW Sec. 17 Twp. 9 Rge. (E)(W) 26

County: Sheridan Total Depth 4060' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Burkey was instructed to plug the well as follows:

309'--8 5/8" Surface casing, cement circulated.

4030'--5 1/2" Production casing cemented on bottom with 150 Sx. Top perforations @ 3863'.

Sand well back to 3800' and set 5 Sx. cement with dump bailer. Pull 5 1/2" casing and squeeze well with 30 sacks gel plus 5 sacks hulls and 100 Sx. cement, staged

Very truly yours,

CP-2

Conservation Division Agent