

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
8-18-69
AUG 18 1969
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated.

Complete Address: Suite 905, Century Plaza, Wichita, Kansas.

Lease Name: Mosier Well No. 2

Location: 150' SW of SE-SW Sec. 6 Twp. 9 Rge. (E)(W) 28

County: Sheridan Total Depth 4075' Oil Well


Gas Well Input Well SWD Well D & A Lost Hole

Mr. Burris was instructed to plug the well as follows:

218'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 1175'.

Circulate hole with heavy mud. Pull DP to 1400' and displace 100 Sx.
cement thru DP. Pull DP to 185' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,


Conservation Division Agent