



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
8-27-73  
AUG 27 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Don Buhrle of Rains-Williamson Oil Co., Inc. has this date requested permission to plug the following described well:

Mr. Buhrle guarantees payment of the plugging fee.

Operator's full Name: Rains & Williamson Oil Company, Incorporated,

Complete Address: 435 Page Court, Wichita, Kansas.

Lease Name: Shaw Well No. 1

Location: NE-SE-NE Sec. 7 Twp. 9 Rge. (E)(W) 28

County: Sheridan Total Depth 4180' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Buhrle was instructed to plug the well as follows:

28 1/2" -- 8 5/8" Surface casing, cement circulated with 170 Sx.  
Top of Dakota section @ 1175'.

Circulate hole with heavy mud. Pull DP to 1400' and displace 110 Cu. Ft. cement thru DP. Pull DP to 300' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

*K. L. Dike*  
Conservation Division Agent