

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
3-26-68
MAR 26 1968
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Johnnie Crow of Garvey Drilling Company has this
date requested permission to plug the following described well:

Mr. Crow guarantees payment of the plugging fee.

Operator's full Name: Petroleum, Incorporated,

Complete Address: 300 West Douglas, Wichita, Kansas.

Lease Name: Mosier Well No. 1

Location: CNW-SE Sec. 6 Twp. 9 Rge. (E)(W) 28

County Sheridan Total Depth 4075 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crow was instructed to plug the well as follows:

179'--8 5/8" Surface pipe, cement circulated with 150 Sx.
Top of Dakota section @ 1240'.

Circulate h ole with heavy mud. Pull DP to 1450' and displace 100 Sx.
cement thru DP. Pull DP to 215' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack bulls and 10 Sx. cement to
bottom of cellar.

Very truly yours,

M. S. Nichols
Conservation Division Agent