



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
4-5-71
APR 5 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Russell Sullivan of Russ Casing Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Linde~~x~~man Well No. 2

Location: SE-NW-SW ^{RC} Sec. 12 Twp. 9 Rge. (E)(W) 28

County: Sheridan Total Depth 4155' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

231'--8 5/8" Surface casing, cement circulated with 160 Sx.
4155'--4 1/2" Production casing cemented on bottom with 200 Sx. Well plugged back to 4080'. Top perforations @ 3300'.

Push plug to 3250', sand back to 3200' and set 4 Sx. cement with dump bailer.
Pull 4 1/2" casing and squeeze well with 5 sacks hulls and 5 sacks gel then 100 Sx. cement from 1450' to 1125' then 22 sacks gel from 1125' to 250' and follow with 25 Sx. cement from 250' to 175' then 3 sacks gel from 175' to 50' and finally 20 Sx. cement from 50' to bottom of cellar.

Very truly yours,

Conservation Division Agent