

State of Kansas



## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
3-19-73  
MAR 19 1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Russ Sullivan of Russ Casing Pulling, Inc., has this  
date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Lindenman Well No. 3

Location: NW-SW-SW Sec. 12 Twp. 9 Rge. (E)(W) 28

County: Sheridan Total Depth 4153' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Sullivan was instructed to plug the well as follows:

253'--8 5/8" Surface casing, cement circulated with 175 Sx.  
4152'--4 1/2" Production casing cemented on bottom no plug back indicated.  
Top perforation @ 3893'.

Push plug to 3850', sand back from 3850' to 3825' and set 3 Sx. cement  
with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls,  
35 sacks gel and 150 Cu. Ft. cement, staged

Very truly yours,

*R. L. Nichols*  
Conservation Division Agent