

15-193-20037-0000

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 13 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Art Hunt of Rains & Williamson Oil Co. has this date requested permission to plug the following described well:

Mr. Hunt guarantees payment of the plugging fee.

Operator's full Name: Lewis M. Mull,

Complete Address: 1625 Wichita Plaza, Wichita, Kansas.

Lease Name: Lyle W. Holley Well No. 1

Location: SW-NE Sec. 2 Twp. 9 Rge. (E)(W) 31

County: Thomas Total Depth 4230' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hunt was instructed to plug the well as follows:

286'--8 5/8" Surface casing, cement circulated with 190 Sx.
Top of Dakota section @ 1400.

Circulate hole with heavy mud. Pull DP to 1625' and displace 100 Sx.
cement thru DP. Pull DP to 300' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hullsands 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent