

15-163-20669-0000

FORM CP-2

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
1-10-77
JAN 10 1977

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Brown of Murfin Drlg. has this date requested permission to plug the following described well:

Mr. Brown guarantees payment of the plugging fee.

Operator's full Name: Murfin Drlg. Co.

Complete Address: 617 Union Center, Wichita, Ks.

Lease Name: Rogers Well No. 1

Location: SW SW NE Sec. 14 Twp. 10 Rge. (E)(W) 16

County: Rooks Total Depth 3660' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole XX

Mr. Brown was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set 65 sk cmt plug at 3367' thru drill
pipe. Heavy mud to 550' set 50 sk cmt plug thru drill pipe. Heavy
mud to 240' set 25 sk cmt plug thru drill pipe. Heavy mud to 40' set
solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Geo. Messer